

BILL OF QUANTITIES**Project:** EPDC Roof Repair**Location:** EPDC Bldg., MIRDC cmpd, General Santos Ave, Taguig, 1631 Metro Manila

Description		QUANTITY		MATERIAL COST		Labor Cost	TOTAL
		No. of Units	Unit	Unit Cost	Total		
1	General Requirements						
1.1.	Mobilization/Demobilization	1	lot				
1.2.	Supply of Personal Protective Equipment and Uniform	1	lot				
1.3.	Hauling of Debris	1	lot				
2	Parapet Wall						
2.1.	Dismantle of Existing Water Proofing	274.8	sq.m				
2.2.	Installation of Water Proofing and roofing sealants	274.8	sq.m				
2.3	Materials						
	a. Acrylic water proofer & sealer	1	lot				
	b. Crack filler	1	lot				
	c. Elastomeric Paint	1	lot				
3	Repair of Gutter						
3.1.	Dismantle of Gutter and Roof Capping	149.4	ln.m				
3.2.	Installation of 0.6 mm Stainless Gutter and Colored Roofing Cap	149.4	ln.m				
3.3.	Rehabilitation of existing Gutter wall downspouts	1	lot				
3.4.	Dismantle of Parapet Wall Flashings	99.6	ln.m				
3.5.	Installation of Parapet Wall Flashings Colored Roofing	99.6	ln.m				
3.6.	Replacement of accoustic board	20	pcs				

Breakdown of Cost**Direct Cost**

Material Cost _____

Labor Cost _____

Mobilization _____

Total Direct Cost

Indirect Cost

OCM (15% of DC) _____

Contractors Profit (10% of DC) _____

Total Direct Cost

Tax (5% of DC + IC)

Total Project Cost

Amount in Words: